



PREFIN. FL COPING ON
45 MIL - TPO FLASHING
3/4" EXT GD PLWD
2X WD BULK

113'-6"
T.O. FINISH BULK

111'-9"
JOIST BRG

EIFS OVER 2X XPS
TYVEK BUG WRAP
1/2" GYP SHTG
6" 18 GA STUDS @ 24" OC.
6 MIL POLY VAPOR RET.

110'-0"
HEAD

PREFIN MET THRU WALL FLASHG
SEALANT

ALUM STOREFRONT W/
1" INSUL GLASS U-0.23

SEALANT
PREFIN. MET SILL

103'-0"
SILL

2X BLOCKING

ADHERED MAX. VENEER
LATH
TYVEK BUG WRAP
1/2" OSB
1/2" XPS
1/2" EXT. GYP SHTG
FIBER GLASS INSUL
6 MIL POLY VR
5/8" GYP BD
100'-0"
FIN. FLE

#4 DOVES @ 18" OC.
#4 BARS

96'-0" TYR
B.O. FTG

45 MIL TPO
1/2" OSB
TAPERED XPS - MIN 2"
(AVERAGE R-VALUE NLT R-20)
1 1/2" X 20 GA STEEL DECK
18K3 JOISTS @ 48" OC.
2X2 ACOUSTIC PANEL CEILING

6" GQT BASE
6x6 GQT
4" CONC. SLAB W/ W1.4 x W1.4 WWF
6 MIL POLY VAPOR RETARDER

10" CONC. FDN WALL W/ #4 BARS
@ 18" O.C. VERTICAL & HORIZ.
2" XPS TO TOP OF FOOTING

Typical Wall Section

Scale: 1" = 1'-0"

Sammy's Submarine Sandwiches
1234 Main Street, Glacier, MN 55199

3/4/2016

10

Revisions:

Trustworthy Builders, Inc
5000 Whiteout Way, Glacier, MN 55199
Contact: Jan Johansson PH: 507-234-5678
Email: JJ01@TrustworthyBuilders.com